

## ADDENDUM NO. 1

BID TITLE: Roadway Milling & Resurfacing: Town Center Blvd., Blatt Blvd., and Island Way

BID NO: 2023-07

DATE: July 31, 2023

To All Bidders:

Bidders for the above referenced Bid shall take note of the following changes, additions, deletions, clarifications, etc., to the bid documents, which shall become a part of and have precedence over anything shown or described otherwise.

### A. CHANGES IN THE BID DOCUMENTS

1. Sheet 2 of project plans, General Notes, Section F, Root Guard or Barrier, is hereby deleted.

#### ~~F. Foot Guard or Barrier~~

- ~~1. Root barrier material shall be the Bio Barrier root guard and shall be twenty four (24) inches wide and installed per manufacturer's instructions. The root pruning shall be performed by a City registered arborist.~~

### B. CLARIFICATIONS

None.

### C. QUESTIONS FROM BIDDERS

1. Q: Is there root pruning and form inspections required before pouring the concrete?  
A: Yes, the root pruning is required. See Sheet 3, General Notes - Section N. Form inspections are required prior to concrete pour.
2. Q: Will there be root barriers installed where the roots lift the concrete?  
A: No. See Section "A" above.
3. Q: Will there be any concrete cylinder or compaction density testing required?  
A: No. Copies of delivery tickets are required reflecting the specified mix.
4. Q: Where exactly will the root pruning be required?  
A: As needed. Staff will identify locations and will be limited to areas where concrete work is proposed (sidewalk and curb ramps replacement).

5. Q: Would the existing ADA ramps require demolition and replacing?  
A: Yes, see project plans for details.
6. Q: Is the detectable warning area a brick paver and not a cast in place?  
A: Yes, see project plans for details.
7. Q: Is the Bidder required to pay permit fees or are they waived by the CITY?  
A: Permits are required but the fees are waived.
8. Q: Can the CONTRACTOR work on all three areas simultaneously or will it need to be one area at a time?  
A: One area at a time.
10. Q: In regard to the milling, would we have to pave back whatever is milled under one shift or can we mill ahead of time and then come in and pave?  
A: Roadway sections milled shall be paved within 48 hours.
11. Q: Will this be for day or night work?  
A: Day work, times are listed in the plans.
12. Q: Will there be any staging areas that can be used by the CONTRACTOR?  
A: The CITY does not own any land in the area, other than the right-of-way.
13. Q: Is the CITY looking to do the concrete work first and then the milling and resurfacing or both simultaneously?  
A: It is up to the CONTRACTOR.
14. Q: When will the job start?  
A: Approximately in October.

#### ATTACHMENTS

1. Mandatory Virtual Pre-Bid Conference Attendance Log

**END OF ADDENDUM NO. 1**  
**All other information remains as originally described in the solicitation.**

**MANDATORY VIRTUAL PRE-BID CONFERENCE**

**Attendance Log**

**Bid No. 2023-07**

**Roadway Milling & Resurfacing: Town Center Blvd., Blatt Blvd., and Island Way**

**Date: July 18, 2023 at 2:00 p.m.**

	<b>First Name</b>	<b>Last Name</b>	<b>Company</b>	<b>Email Address</b>
1	Paul	Emends	Florida Blacktop, Inc.	paul@floridablacktopinc.com
2	Joel	Espinosa	ADEC Construction, Inc.	Joel.Espinal@adeconstructioninc.com
3	Steven	Espinal	American Design Engineering & Construction, Inc	steven.espinal@adeconstructioninc.com
4	Matt	Stone	Pave Co.	mstone@paveco.com
5	Joshua	Marfleet	M&M Asphalt Maintenance	jmarfleet@allcountypaving.com
7	Daniel	Sanchez	General Asphalt	daniel@generalasphalt.com
8	Clint		Weekley Asphalt	clint@weekleyasp.com
9	Mike	Dever	Atlantic Southern Paving	mdever@atlanticsouthernpaving.com
10	Xavier	Rodriguez	JDCW Estimating	jdcwestimating@gmail.com
11	Meagan	Martin	R and D Paving	meagan@randdpaving.com