

ADDENDUM NO. 2

BID TITLE: Sidewalk Repairs and Pavement Marking Refurbishment Surtax-Funded Municipal Transportation Project No. BC-Weston-FY2020-00004

BID NO: 2023-12

DATE: December 18, 2023

To All Bidders:

Bidders for the above referenced Bid shall take note of the following changes, additions, deletions, clarifications, etc., to the bid documents, which shall become a part of and have precedence over anything shown or described otherwise.

A. CHANGES IN THE BID DOCUMENTS

1. Document 00010, Notice To Bidders, first paragraph under the bid title has been changed to read as follows:

Bids shall be accepted from qualified licensed general contractors to furnish all labor, supervision, equipment, supplies, tools, permitting, safety measures and all other necessary incidentals for the construction of sidewalks along sections of Lakeview Drive in the City of Weston, Florida ~~to provide connections to a safe school route~~. Scope of work includes clearing and grubbing, construction of sidewalk and curbing, ADA curb ramps and pavement markings.

B. CLARIFICATIONS

None.

C. QUESTIONS FROM BIDDERS

1. Q: Would a FDOT Prequalification license suffice in lieu of General Contractor license requirement?

A: No.

2. Q: There is a Manhole within the sidewalk replacement limits, it will have to be adjusted. On which line item we allocate the cost of Utility adjustments?

A: If a manhole needs to be adjusted, the CITY's utility contractor will make the adjustments needed in coordination with the awarded contractor.

3. Q: On the drawings, Sheet 2, Note B Concrete Curb, Sidewalk or Walkway: Note 2. Base shall be a minimum of four (4) inch thick well compacted limerock base. Is new limerock material required for base or compact existing base material is ok?

A: New limerock material will only be required for new sections of concrete proposed, where there is no existing limerock base. Compacting the existing base material is acceptable under existing sidewalk proposed for replacement.

4. Q: On the drawings, Sheet 2, Note C Root Guard or Barrier Note 1: Root barrier material shall be the Bio-Barrier root guard and shall be twenty-four (24) inches wide and install per manufacturer's instructions. There is no line item for Root Barrier installation on the bid items. Where do we allocate the Root Barrier installation cost, or Root Barriers are not required?

A: Root barriers are not required.

5. Q: For the striping: would the CITY allow sand blasting or water blasting instead of grinding?

A: No, the City Code only allows for grinding.

6. Q: Approximately 80% of the sidewalks are behind the banks where the trees are located and the concrete trucks cannot reach; will the CITY consider allowing pumps for the concrete?

A: Yes.

ATTACHMENTS

1. Mandatory Virtual Pre-Bid Conference Attendance Log

END OF ADDENDUM NO. 2

All other information remains as originally described in the solicitation.

**MANDATORY VIRTUAL PRE-BID CONFERENCE
ATTENDANCE LOG
Bid No. 2023-12
Sidewalk Repairs and Pavement Marking Refurbishment
Surtax-Funded Municipal Transportation Project No. BC-Weston-FY2020-00004
Date: December 7, 2023 at 11:00 a.m.**

	First Name	Last Name	Company	Email Address
1	Todd	Kneisel	Heavy Civil, Inc.	tiffany@heavycivilinc.com
2	Albert	Morejon	Absolute Construction Services	albertacs@gmail.com
3	Xavier	Rodriguez	J&D Concrete Works Corp.	jdcwestimating@gmail.com
4	Elliot	Ikel	Weekley Asphalt Paving, Inc.	elliott@weekleyasp.com
5	Rene	Ochoa	Homestead Concrete & Drainage	rochoa@homesteadconcrete.com
6	Javier	Rodriguez	RoGar Management & Consulting	dekorallc@gmail.com
7	Andy	Ramsaywack	VPR Construction	andy@vprconstructioncorp.com
8	Mariana	Alegria	R.J. Engineering Construction	rjengineeringfl@gmail.com
9	Tom		Danto Builders, LLC	Tom@dantobuilders.com
10	Sandra	Chacon	SC Contractors, LLC	chacon.sandra@gmail.com
11	Frank	Rivera	National Traffic Solution	frankjr@trafficsolution.us
12	Jessica	Fernandez	AJ Dumping and More	Info@ajdumpingandmore.com
13	Steven	Espinal	A.D.D. Construction	